


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Mc Pherson County. Sec. 3 Twp. 19 Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NE/4 NE/4
Lease Owner George Hess
Lease Name Frank Hill Well No. 3
Office Address 505 North Charles, Mc Pherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 10-18 1969
Application for plugging filed 5-20 1970
Application for plugging approved 5-20 1970
Plugging commenced 5-20 1970
Plugging completed 5-22 1970
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 2970' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		1,264'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Drilled but not completed.
Pipe collapsed at 2700'. Mudded hole to 155 feet.
Made 10' of rock bridge. Dumped 25 sx of cement.
Mudded hole to 40'. Made 10' of rock bridge. Dumped 10
sx of cement, filling to the bottom of the hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970 5-27-1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501


STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1970

My commission expires January 5, 1974

Judy Lamb
Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

October 21, 1969

COMPANY: GEORGE R. HESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: FRANK HILL #3
 LOCATION: C-N/2 NE/4 NE/4 3-19-2
 McPherson County, Kansas
 COMMENCED: October 11, 1969
 COMPLETED: October 18, 1969
 ELEVATION: 1569 K. B.

0	to	70	Shale
70	to	85	Sand
85	to	95	Blue Shale
95	to	145	Shale
145	to	600	Shale & Lime
600	to	860	Lime
860	to	1240	Lime & Shale
1240	to	1800	Shale & Lime
1800	to	1995	Lime
1995	to	2295	Lime & Shale
2295	to	2347	Lime
2347	to	2585	Lansing
2585	to	2717	Lime
2717	to	2956	Lime & Shale
2956	to	2970	Mississippi
		2970	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 21 1970
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 1/4 in. hole to 143 ft. and run 143 ft. of 8 5/8 in. surface pipe, cemented on bottom at 140 ft. with 90 sacks of cement. Plug down at 12:15 P. M., October 11, 1969. Cut 7 7/8 in. hole to 2970 and run 2965 ft. of 4 1/2 in. pipe, cemented with 90 sacks of cement 7 ft. off bottom at 2963 ft. Plug down at 3:30 P. M. on October 18, 1969 and spotted with 25 barrels of oil behind the pipe.

TOPS: Lansing - 2347' Mississippi - 2956'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Flouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is true and correct copy of log on your Frank Hill #3, located on the C-N/2 NE/4 NE/4 3-19-2, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Flouffe
 H. J. Flouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 31 day of October, 1969.

Johnnie L. Schmidt
 Johnnie L. Schmidt, Notary Public

