

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County. Sec. 3 Twp. 19 Rge. 2W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE SE NE

Lease Owner F Bennett-Gould

Lease Name Finkle Well No. 1

Office Address c/o Chas. Gould 5830 N Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed 19

Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole back from 2997 to 2955 dumped 5 sacks cement
Bailed fluid and mudded hole to 165' set 10' rock bridge mixed and dumped
15 sacks cement mudded to 20' rock bridge and dumped 5 sacks cement.

RECEIVED 3-16-1959
STATE CORPORATION COMMISSION
MAR 16 1959
CONSERVATION DIVISION
WELL PLUGGING

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roy L. Myers
Box 364, Great Bend, Kansas Sec. Treas.
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of March, 19 59

My commission expires December 18, 1962

Juanita R. Myers
Notary Public.

PLUGGING
FILE SEC 3 T 19 R 2W
BOOK PAGE 101 LINE 16

C O P Y

Finkle #1

Company: -Bennett and Gould
 Contractor: -SeRoBee Drilling co., Inc.
 Commenced: -4-7-58
 Completed: -4-19-58
 Total Depth: -2969'
 Initial Prod: -Dry Hole

Location: NE SE NE Sec.3-19S-
 Range 2W
 McPherson County, Ks
 Elevation: Rotary Bushing 1565'
 Casing: 8 5/8" - 165'
 cemented with
 150 sax

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 70	Rock and Surface Clay
70 - 1105	Lime and Shale
1105 - 1665	Shale and Shells
1665 - 1795	Lime and Shale
1795 - 2095	Lime
2095 - 2245	Sandy Shale
2245 - 2342	Shale and Shells
2342 - 2420	Lime
2420 - 2500	Kansas City Lime
2500 - 2715	Lime
2715 - 2740	Shale
2740 - 2940	Lime and Shale
2940 - 2955	Cherty Conglomerate
2955 - 2969	Mississippi Lime
2969	Rotary Total Depth

2969 - 2997 ft new open hole CCG

We hereby certify the above and foregoing to be a true and correct copy of the log on the Finkle #1, located in the NE SE NE, Section 3-19S-2W, McPherson County, Kansas.

SEROBEE DRILLING CO., INC.

Paul S. Septer
 Paul S. Septer

Subscribed and sworn to before me this 28 day of April, 1958.

Lila W. Sumner
 Notary Public

My commission Expires 7-25-60.

STATE CORP. REGISTRATION

MAY 19 1958

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 3 T 19 R 2W
 BOOK PAGE 101 LINE 16