

Re

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

McPherson County. Sec. 28 Twp. 19S Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE

Lease Owner K & P Oil Co.

Lease Name Bair Well No. 2

Office Address 524 Kennedy Bldg (P O Box 682) Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 11-18-57 19

Application for plugging filed 19

Application for plugging approved March 17 1961 19

Plugging commenced March 15 19 61

Plugging completed April 2 19 61

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Jan 3 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation 2923 Depth to top Bottom Total Depth of Well 3017 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi		2923	3017	5 1/2	3016 1/2	2131

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back 10' in pipe with gravel. Dumped 5 sacks of cement.  
Shot pipe off at 2131'. Pulled pipe and mudded hole to 200'.  
Set rock bridge and finished filling hole with ready mix cement.

5-23-1961

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bert Self  
Address R R #4 Hutchinson, Kans

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 61

My commission expires August 12, 1961 Notary Public.



COMPANY: K & F Oil Company  
 CONTRACTOR: Mallard Drilling Company  
 FARM: Bair # 2  
 LOCATION: SW NW NE Sec. 28-19-1W  
 Mc Pherson, County, Kansas  
 COMMENCED: November 11, 1957  
 COMPLETED: November 18, 1957

0	to	90	Sand
90	to	208	Shale
208	to	580	Shale
580	to	780	Lime
780	to	1525	Shale
1525	to	1715	Shale and lime
1715	to	2025	Lime
2025	to	2395	Shale and lime
2395	to	2570	Lime
2570	to	2685	Shale and lime
2685	to	2800	Lime
2800	to	2923	Shale and lime
2923	to	2993	Mississippi
2993	to	3017	Mississippi
		3017	E.D.

Set 208 feet of 8 5/8" surface pipe. Cemented with 135 sacks cement.  
 Set 5 1/2 inch at 3016 1/2'. Cemented with 100 sacks cement, 10 in rat hole.  
 TOPS: K.C. -- 2845 Mississippi -- 2923  
 Measurements taken from R.D.B. R.D.B. 5 1/2' from ground level.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Bair #2, Mc Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 21st day of November 1957.

Robert G. Hank

My commission expires Nov. 16, 1959

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1961

CONSERVATION DIVISION  
Wichita, Kansas

Re

K &amp; P OIL CO -- PAIR # 2

Canton, Kansas

28-19-1W

February 28 1961.

Filled 5 1/2" casing with gravel back to 2940 feet.  
 Put in 5 sacks of cement on top of gravel.  
 Shot casing off at 2400 feet. Pipe tight and could not  
 pull it. Mixed and pumped in with Halliburton pump  
 truck 50 sacks of mud and 25 sacks of hulls trying to  
 circulate around casing. Never got circulation.  
 Pumped 40 barrels of oil down and out of casing and  
 shut down.

March 14 1961

Casing still stuck tight: Shot casing off at 2300 ft.  
 Still tight, tried again to circulate with Halliburton  
 pump truck using 30 sacks of mud and 15 sacks of hulls.  
 Still couldn't circulate around 5 1/2" casing. Called  
 McCullough Tool Company and ran Magna-Tector (free-point)  
 tool and found pipe free at 2100 ft. and froze at 2150'  
 Shot pipe off at approx. 2120'. Pipe loose now.

March 15 1961

Pulled 5 1/2" casing out of well: Mudded hole to 200'  
 then filled to surface with ready-mix concrete as per  
 State Plugger's instructions.

Report by:

Cameron Pence

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 23 1961

CONSERVATION DIVISION  
 Wichita, Kansas