

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY McPherson SEC. 12 TWP. 19S RGE. 1W E/W
Location as in quarters or footage from lines:

S/2 SE/4 NW/4

Locate Well
correctly on above
Section Platt.

Lease Owner Eugene W. Bryan, Sr.
Lease Name Harold L. Carey #1 Well No. _____
Office Address R.R. #1 Box 59 Canton, Kansas 67428
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-21-81
Plugging completed 11-24-81
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marlan W. Unruh

Producing formation _____ Depth to top _____ bottom _____ T.D. 2912'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	159'	none
				4-1/2"	2910'	2047'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 2825' and set 4 sacks cement. Shot pipe @2388',
2185' and 2070. Pulled a total of 35 joints of pipe. Set rock bridge from 200' to
180' and ran 3 yards of ready-mix cement. IDENTIFIED PLUGGING.
EXTENDED to base of cellar.

Plugging Completed.

RECEIVED

STATE CORPORATION COMMISSION

DEC 21 1981 12-21-81

CONSERVATION DIV (If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Keiso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Keiso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Keiso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 81



Irene Hoover
Notary Public.

My Commission expires: _____

15.113.20492.00.00

APP 92-SE/4-NW/1

STATE	KANSAS	2-1-27	MAP NO.	S-T-R	12-19S-1W	WF
OPER	BRYAN & GEIS			SPOT	APP NE NE NW	INIT
	RT 1, CANTON, KS	67428		CO	MCPHERSON	WFI
WELL	1 HAROLD L CAREY			ELEV	1532 KB, 1527 GR	FIN
CONTR	TRIANGLE DRLG					

FIELD WC - 3/4 MI NW DOLES PARK (MISS)
 4PT CAOF 205 MCFGPD + 20 BWPD (MISS)
 IP 2854-2898 OA API 15-113-20492
 SPUD 11-25-77, 8 5/8" @ 159 w/100, Geol Harry Hopkins
 DST 1 (MISS) 2854-74, op20, si30, op30, si30, GTS/
 Immed, F 21 MCFG/40", Rec 110' Mud, ISIP 580, FP
 73-64/73-73, FSIP 607
 RTD 2912, 4 1/2" @ 2910 w/70
 Perf (MISS) 20/2854-74, 250 Gal A, F 135 MCFG, 6/
 2896 1/2-2898, 250 Gal A, F 70 MCFG
 4PT CAOF 205 MCFGPD + 20 BWPD, MISS 2854-2898 OA

KB LOG TOPS:
 HEEBNER 2032 - 500
 TORONTO 2048 - 516
 DOUGLAS 2059 - 527
 BROWN LM 2208 - 676
 LANSING 2271 - 739
 CHEROKEE 2819 - 1287
 PENN CONGL 2836 - 1304
 MISS 2848 - 1316
 OSAGE 2892 - 1360
 RTD 2912 - 1380
 TD IN MISS
 COMP ISSUED 2-6-78

RECEIVED
 STATE CORPORATION COMMISSION
 MISS - UNNAMED FIELD - DISCOVERY

OCT 5 1981

CONSERVATION DIVISION
Wichita, Kansas

Petroleum Information Corporation
 Copyrighted 1978 Reproduction Prohibited

Mr. Kelso:

As per Telecon request of Tuesday, Sept. 22, to plug the above well, I am enclosing the above info. You also requested a deadline date to be notated on this correspondence, which is November 27, 1981.

Thank You
 Gene Bryan Sr.

330 SNL
330 WFL
6 31/3 A NW