

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15 097-21,073-0000 (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171  
ADDRESS 155 N. Market, Suite 1000, Wichita, KS 67202 PHONE # (316) 269-7600  
LEASE (FARM) Nichols "F" WELL NO. 1 WELL LOCATION 1980' FNL COUNTY Kiowa  
3300' FSL 3300' FEL  
SEC. 1 TWP. 30S RGE. 18 ~~SSSS~~ (W) TOTAL DEPTH 5050' PLUG BACK TD 5002'

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8-5/8" SET AT 475' CEMENTED WITH 375 SACKS  
CASING SIZE 4 1/2" SET AT 5046' CEMENTED WITH 200 SACKS  
PERFORATED AT 4790'-94' & 4944'-50'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 25 sxs 60-40 Poz mix down csg followed  
by rubber plug, stop plug at ± 4700'. Cut csg. at ± 4000' & POOH. Plug surface csg  
w/3 sxs hulls, 15 gel, 50 sxs 60-40 Poz, 1 sk hulls, 10 gel, 1 hulls, 8-5/8" plug,  
150 sxs 60-40 Poz mix.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Collins PHONE # (316) 886-5605  
ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Great Bend Casing Pullers Inc. LICENSE NO. 4685CP  
ADDRESS P.O. Box 768, Great Bend, KS 67530 PHONE # (316) 793-9711 1987

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jerry Collins  
(Operator or Agent)

DATE: \_\_\_\_\_

①

RECEIVED  
STATE CORPORATION COMMISSION  
4685CP  
11-6-87  
CONSERVATION DIVISION  
Kansas

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

November 6, 1987

FEB 06 '88

WELL PLUGGING NOTICE

EXPIRES

Nichols "F" #1  
3300' FSL 3300' FEL  
Sec. 01-30S-18W  
Kiowa County

TXO Production Corporation  
155 N. Market, Ste. 1000  
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist*  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760