

State of Kansas



15.009.14722.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1972
CONSERVATION DIVISION
Wichita, Kansas

6-28-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. W. J. DeVaney of Cities Service Oil Co. has this
date requested permission to plug the following described well:

Mr. Cities Service Oil Co. guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas 67530

Lease Name: R. Bryant "A" Well No. # 2

Location: NW SW NW Sec. 25 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3295 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

10 3/4" csg. 242' Cwc.

Sanded hole back to 3240' & dumped 6 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 25 sax mud, & 124 sax

cement with Sun Cementing Company's pump truck, cementing from 340'

to base of cellar.

Very truly yours,

Don L. Lewis
Conservation Division Agent