

State of Kansas



15-009-21383-0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS, 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 19 1978

CONSERVATION DIVISION  
Wichita, Kansas

5-19-1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg. Russell, Kansas 67665

Lease Name: Deutch "B" Well No. 1

Location: N/2 S/2 SW Sec 10 Twp. 16 Rge. 13  (W)  X

County: Barton Total Depth 3374' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 500'.

Fill hole with mud and spot 25 sx cement at 240'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.

2 sx cement in rat hole. 2 sx cement in mouse hole.

262' of 8 5/8" surface casing cement circ.

Very truly yours,

Deane J. Rubin  
Conservation Division Agent