

State of Kansas



15-009-22109-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Shawn of Sage Drlg. Co., Inc. has this
date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Sage Drlg. Co., Inc.

Complete Address: 222 Sutton Place, Wichita, Kansas 67202

Lease Name: Ochs Well No. 1

Location: 100' SW Of C NE $\frac{1}{4}$ Sec. 10 Twp. 16 Rge. 13 (EX(W) X

County: Barton Total Depth 3391' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 480'.

Fill hole with mud and spot 30 sx cement at 300'.

Fill hole with mud to 40' and $\frac{1}{2}$ sx hulls, plug, and

10 sx cement. 5 sx cement in rat hole.

318' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 7 1980

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

10-7-1980

Quane L Rankin
Conservation Division Agent