

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1973
7-16-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fornbsy of Garvey Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Fornbsy guarantees payment of the plugging fee.

Operator's full Name: Petroleum., Inc.

Complete Address: 300 w. Douglas, Wichita, Ks.

Lease Name: McKinley -B- Well No. 1

Location: A-GSL- SWSE. Sec. 2 Twp. 28S Rge. 20 (E)(W) X

County: Kiowa Total Depth 4922 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fornbsy was instructed to plug the well as follows:

603 ft. 8 5/8 surface cemented with 400 sacks
Pump 50 sacks cement to 350 ft. mud to 40 ft. plug,
1/2 sack hulls and 15 sacks cement to surface. 2 sacks
cement in rat hole and 2 sacks cement in mouse hole.

Pumped by, Halliburton Cementing Co.

Great Bend, Ks.

Very truly yours,

[Signature]
Conservation Division Agent