

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

17-March 1982
RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1982

CONSERVATION DIVISION
Wichita, Kansas 3-23-1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-097-20865

Dear Sir:

Mr. Jim Service of Santa Fe Drilling Co has this date requested permission to plug the following described well:

Operator's Full Name: Dave Thomas Jr.

Complete Address: P.O. Box 2026 Farmington, New Mexico 87401

Lease Name: Brensing Well No. 1

Location: 723' FWL-660' FNL Sec. 8 Twp. 28 Rge. 20 (E) (44)

County: Kiowa Total Depth: 5050'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Service was instructed to plug the well as follows:

There is 678' of 8 5/8" surface casing cement circulated. The anhydrite was topped at 1318', 1st plug at 1280' with 60 bbl of cement. 2nd plug push rubber plug to 660' + pumped 35 bbl of cement on top of it. 3rd plug at 40' to 0' on solid bridge with 10 bbl of cement. Then circulate 10 bbl cement in rat hole + 5 bbl of cement in mouse hole. The cement was pumped through drill pipe with Halliburton, accomplishing the plugging.

Very truly yours,

Paul A. Luther
Conservation Division Agent