

State of Kansas



15.113.30020.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 5 1967

CONSERVATION DIVISION  
Wichita, Kansas

10-5-1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Small of Art Small has this

date requested permission to plug the following described well:

Mr. Small guarantees payment of the plugging fee.

Operator's full Name: Art Small

Complete Address: R.R. # 3 Salina, Kansas

Lease Name: Goering Well No. # 1

Location: E/2 NW Sec. 13 Twp. 19 Rge. 3 (R) (W)

County McPherson Total Depth 2967' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Small was instructed to plug the well as follows:

8 5/8"-158'-Circulated w/cement. 5 1/2"-2967'-Cemented. Top Perf. 2342'.

Plug set at 2300'. 5 Sax. cement 2300' to 2250'. Mud 2250' to 170'.

Bridge 170' to 160'. 2 1/2" Plug. from 160' to 150' with ready mix cement.

Pulled 2000 ft 5 1/2" pipe. 10 Sax. cement 30' to 0.

Very truly yours,

Hugh Scott  
Conservation Division Agent