

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name K & E Drilling, Inc.

Complete Address 816 Union Center Bldg., Wichita, Kansas. 67202

Lease Name Parkin Well No. 8

Location C-SE-SE Sec. 3 Twp. 30S Rge. 18 (E) (W) W

County Kiowa Total Depth 4950

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Nicholas Casing Pulling.

Address Box 373 Genesco, Kansas. 67444 License No. 711

Operation Completed: Hour 12:45 pm Day 16 Month 3 Year 1979

The above well was plugged as follows:

409' 8 5/8" casing. 4 1/2" casing set at 4950' w/ 100 sax cement. Top
pref.,. at 4890'-94'. Sand back to 4670' top sand w/ 4 sax mixed cmt.
w/ dump bailer. Pull 3530' 4 1/2" casing. Halliburton mixed & pumped
5 sax hulls, 25 sax gel, released plug, mixed & pumped 125 sax 50/50
posmix cement w/ 6% gel to top of casing. Shut in w/ 800# pressure.

RECEIVED
STATE CORPORATION COMMISSION
3-20-79
MAR 20 1979

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas

DATE 3-20-79
INV. NO. 9292-W