

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name F. E. Delgo, Inc.

Complete Address 86 Union Center Bldg. Wichita, Kans. - 67202

Lease Name Jarvis Unit Well No. 3

Location C-5E- Sec. 4 Twp. 30^S Rge. 18 (E) 4 (W)

County Flores Total Depth 5008

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373 Seneca, KS. 67444 License No. 711

Operation Completed: Hour 11:5 pm Day 8 Month 9 Year 1978

The above well was plugged as follows:

560' 8 5/8" Casing w/ 300 sack Cement - 5 1/2" Casing set @ 5003'
w/ 100 sack Cement in 5' open hole - Sand back to 4995' - top sand
w/ 5 sack mixed Cement w/ dump. hauler Pull 2650' - 5 1/2"
Casing - Set rock bridge from 25.5' back to 245' - dump
appr. 3 1/2 yard ready mix Cement to 5' below ground level
This is approximately the way it was done. Metered Cement
was 1313 - noway is 7 sack metered Cement of 1313 - is 7 yard
to. Was told bridge @ 520' - I just happened by. Never

I hereby certify that the above well was plugged as herein stated.

got a call when they would plug
off - the top -

Signed: [Signature]
Well Plugging Supervisor

Hildingers ready mix - Greensburg KS - 67054 SEP 11 1978
9-11-78

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name F. E. Drilling, Inc.

Complete Address 816 Union Center Bldg, Wichita, Kans - 67202

Lease Name Parkin Unit Well No. 3

Location C - S 8 - Sec. 4 Twp. 30 Rge. 18 (E) (W) 4

County Finney Total Depth 5008

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373, Geneseo, Kans - 67444 License No. 711

Operation Completed: Hour 1:15 pm Day 8 Month 9 Year 1978

The above well was plugged as follows:

560' - 8 5/8" Casing w/ 300 sac Cement - 5 1/2" Casing set @ 5003'
w/ 100 sac Cement - 5' o.p. hole - Sand back to 4995' - mix
& dump on top of sand w/ dump bailed 5 sac Cement fill
to 50' - 5 1/2" Casing - Set rock bridge from 530' back to 520'
dump 8 yard ready mix in 8 5/8" Casing to 5' below
Ground level - - returned Cement -

Lidingers, ready mix, Greenburg, Kans - 67054

This is the way they were told to do it -

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature] SEP 11 1978
Well Plugging Supervisor

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 9-13-78

INV. NO. 8048-U