

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed September 22, 1967.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1967
10-5-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas 67202

Lease Name Parkin Well No. # 1-7

Location C SE NE Sec. 7 Twp. 30 Rge. 18 (E) (W)

County Kiowa Total Depth 5270' 5070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Graham-Michaelis Drilling, Inc.

Address: 211 N. Broadway, Wichita, Kansas 67202 License No.

Operation Completed: Hour 4:45 PM Day 4th Month Oct. Year 1967

The Above well was plugged as follows:

429' of 8 5/8" surface pipe, cement circulated with 325 sacks. Hole was
filled with drilling mud to 400', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 400', and cemented with 25 sacks, through the drill
pipe, with cement from 390' to 315'. Hole was filled with drilling mud to
50', 2nd cementing plug bridged with 1/2 sack of hulls on fluid at 40', and
cemented with 15 sacks, with cement from 40' to the base of the cellar.

Rat hole bridged and cemented with 2 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE

INV. NO.