

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
RECEIVED
STATE CORPORATION COMMISSION

OCT 04 1976

10-4-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 19483.0000 (of this well)

Operator's Full Name National Cooperative Refinery Assn.

Complete Address Box 6 Great Bend Ks 67530

Lease Name Peters Well No. 11

Location SE NE NW Sec. 13 Twp. 20 Rge. 11 (W)

County Barton Total Depth 3274

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box # 176 Chase Kans 67524 License No. 683

Operation Completed: Hour 10³⁰ AM Day 29 Month 9 Year 1976

The above well was plugged as follows:

Sanded Back to 3000' @ 5sx Cement @ Dump Bailer. -

Squeezed thru 8 5/8" Surface Casing @ 3sx Hulls, 15sx

Mud Gel, Plug @ 100sx Cement. -

Max Pressure. 300# Shut in Pressure 100 #

Recovered 1805' of 5 1/2" casing. -

Plugged Back to 3054' @ Top Perforation @ 3020'

3266' of 5 1/2" casing cemented @ 75sx Cem. -

151' of 8 5/8" Surface Casing cement circ @ 150sx Cem

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Durand L Rankin
Well Plugging Supervisor

DATE 10-5-76

INV. NO. 3940-W