

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-45

LOCATION 22E-SF-21E

SEC. 13 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease Petes

Operator Nath. Co-op. Refinery, Cas, n Address 820 N. Natl. Bldg. Wichita-Kans

Field _____ County Barton

Total Depth 3700 Feet. Plugging Contractor - West Supply Co
Chas. Mann

(Describe briefly the manner in which the well was plugged) Account #14

Surface Pipe 8 3/8 - 160 ft - Circulated with cement
3/4 casing set at 3284 ft - Cemented with 75 sacks cement
Plugged back to 3250 ft with sand - Pumped 5 sacks
& cement at 3250 ft - Shot off & pulled the 3/4 casing
& Pumped in 60 bbls of heavy sand - Set rock bridge
& 15 sacks of cement at 160 ft - mud to 35 ft -
Plug & 15 sacks cement at the surface

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1953

CONSERVATION DIVISION
Wichita, Kansas

C. H. Stough
District Conservation Agent

Date 11-14-53

PLUGGING

FILE SEC 13 T 20 R 11W
BOOK PAGE 134 LINE 45

11-17-53