

15.009.14567.0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

3-2-70

Operator's Full Name ~~Austin~~ Robert L. Austin

Complete Address Box 159 Stafford, Kansas

Lease Name Houser Well No. 1

Location SW NW Sec. 16 Twp. 20 Rge. (E) (W) 11

County Barton Total Depth 3304'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 105 Chase, Kansas License No. 436

Operation Completed: Hour 4P Day 20 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3304' 8 5/8 csg set at 270' cwc

5 1/2 csg set at 3287' cw 100 sk cmt.

5 1/2 csg squeezed at 400' and circ. to surface. No pipe recovered.

Filled 5 1/2 csg W/sd (3280-3304) dumped 5 sk cmt W/dump bailer. (3240-3280)

Mid to 480'. set wood plug, rock and sand, (465-480)

Dumped 3 yds readymix cmt (0-465)

I hereby certify that the above well was plugged as herein stated.

Signed: Red L. Massey  
Well Plugging Supervisor

INVOICED

DATE 3/3/70  
INV. NO. 1532-W