

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-009-22745.0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Petroleum Energy, Inc.

Complete Address 105 N. Main St. Suite 415, Wichita, Ks. 67202 # 6690

Lease Name Hansen "A" Well No. 1

Location C-N2 N/2 NE Sec. 16 Twp. 20 Rge. 11 (East) (West)

County Barton Total Depth 3293'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Barlow Well Service

Address P.O. Box 868, Great Bend, Ks. 67530 License No. 987

Operation Completed: Hour: 3:30PM Day: 29 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 289' S.P. cas. w/175 sacks common. 5 1/2" set at 3290' w/125 sacks common.
Open hole to 3293'. Plugged bottom w/20 sacks cement. Shot pipe 1 time
+ recovered (1906). Ordered 140 sacks 50% posmix - 4% Gel. - 3% vol. G., 5 sacks hulls,
15 sacks Gel., 4 8 5/8" plug. Pumped in 8 5/8" - 4 hulls, 12 sacks Gel., 70 sacks cement,
3 sacks Gel., 1 sack hulls, released plug & followed w/20 sacks cement.

Maximum pressure 500 pounds.

Amount of Surface Casing: 289' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1982 10-12-82

INVOICED

DATE 10-20-82

DIV. NO. 1434-W

Signed: _____
Conservation Division Agent