

15.009.04852.0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS  
1-12-67

Operator's Full Name Tomlinson-Kathol, Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name Scheufler Well No. # 5

Location SE SE SE Sec. 16 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3305

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. # 436

Operation Completed: Hour 1:30 PM Day 9 Month 1 Year 1967

The Above well was plugged as follows:

8 5/8" 324' Cwc.  
Sanded hole back to 3220' & dumped 3 sax cement with dump bailer. Pulled pipe.  
Mudded hole to 300', set 10' rock bridge, & displaced 25 sax cement. Mud to  
40', set rock bridge, & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Truman  
Well Plugging Supervisor

INVOICED

DATE 1/12/67  
INV. NO. 4593-u