

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
Wichita, Kansas

10-18-1978

Operator's Full Name Decker Petroleum, Inc.

Complete Address P.O. Box 352, Canton, Kansas 67428

Lease Name Nigg Well No. 1

Location App. C w/2 NW NE SE Sec. 24 Twp. 19 Rge. 1 (E) (W) X

County McPherson Total Depth 2990'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Holt Lamb Casing Pulling, Inc.

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 1 PM Day 13 Month October Year 1978

The above well was plugged as follows:

8 3/4" - 146' - cement circulated 4 1/2" - 2989' - 50 sacks PB-TD - 2940 Perf 2990'
Hole Filled with sand to 2900' and cemented with 4 sacks
Cement. Rock bridge set from 180' to 170' and hole cemented
with 25 sacks. Hole Filled with mud to 40'. Rock bridge set
From 40' to 30' and hole cemented to base of cellar with 10
Sacks cement.
900' of 4 1/2" recovered.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10-20-78

INV NO. 9336-W