


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 25 Twp. 20S Rge. 11 ~~(E)~~ W (W)
Location as "NE/CNW/SW" or footage from lines 330' N. - 1320' W of W/4 Cor.
Lease Owner Cities Service Oil Company
Lease Name R. Bryant "A" Well No. 4
Office Address Box 308, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 29 19 37
Application for plugging filed November 30 19 71
Application for plugging approved December 3 19 71
Plugging commenced December 21 19 71
Plugging completed December 23 19 71
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Arbuckle Depth to top 3274' Bottom 3305' Total Depth of Well 3305 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	194'	-0-
				7"	3274'	1636'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug Back with Sand	3305-3250'
6 Sacks Cement	3250-3220'
Squeezed with 20 Sacks Gel	3220- 260'
3 Sacks Hulls	260- 250'
125 Sacks Cement	250- 0'


RECEIVED 12-28-1971
STATE CORPORATION COMMISSION
DEC 28 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company
Address 1920 16th, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
W. J. Devaney (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 308, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 27th day of December, 19 71



My commission expires June 3, 1973 _____ Notary Public.

WELL RECORD

Company (ITIO) Cities Service Oil Co. Well No. 4 Farm Rose Bryant "A"
 Location 1320' west and 330' north of ^{E/4} Corner Sec. 25 T. 20 R. 11W
 Elevation 1754 County Barton State Kansas
 Drig. Comm. August 7, 1937 Contractor Schoenfeld, Hunter & Kitch Drilling Co.
 Drig. Comp. August 26, 1937 Acid 2000 gallons
 T. D. 3305' Initial Prod. 1418 oil, 0 water, 2 1/2 hours - Physical Test

CASING RECORD:

10-3/4" @ 194' cem. 175 sacks
 7" @ 3274' cem. 200 sacks

Top Kansas City 3010'
 Top Arbuckle 3274'
 Penetration 31'
 Total Depth 3305'

FORMATION RECORD:

sand - surface 90
 clay 95
 sand & red rock, medium 194
 shale 400
 red bed & shale 675
 shalls & red rock 885
 shale 1130
 shale & shalls 1426
 shale & salt 1700
 shale & shalls 1883
 shale & lime 1963
 lime & shale 2063
 shale & lime shalls 2335
 lime & shale 2457
 shale 2625
 lime 3272
 lime, hard 3284
 lime, grey, hard 3300
 lime, grey, medium 3305 T. D.

Vertical Tests: 670' 10
 1215' OK
 2500' 10

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 1 1971
 CONSERVATION DIVISION
 Wichita, Kansas

3010
 1754
 1256
 3274
 1254
 1328