


15-009-20173-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 10 Twp. 16S Rge. XX 13 (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner Three G Oil, Inc.

Lease Name Ehrlich Well No. 1

Office Address 1101 Wichita Plaza Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 7 1968

Application for plugging filed Verbal Authority 1968

Application for plugging approved Verbal Authority 1968

Plugging commenced January 7 1968

Plugging completed January 7 1968

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,350 feet (rotary total depth) to 500 feet. Set bottom plug at 500 feet and cemented with 30 sacks cement by Sun Cementing Co. pump truck. Filled hole with heavy rotary mud to 270 feet. Set plug at 270 feet and cemented with 25 sacks cement by Sun Cementing Co. pump truck. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement by Sun Cementing Co. pump truck, 2 sacks cement in rat hole.

RECEIVED 1-11-1968
STATE CORPORATION COMMISSION
JAN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.

Address 200 North Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer

200 North Main St., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of January, 1968

My commission expires April 21, 1971

Martha Hartpence
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-009-20173-0000

COMPANY Three G Oil, Inc.
 FARM Ehrlich NO. 1

SEC. 10 T. 16S R. 13W
 LOC. NW NE SE

TOTAL DEPTH 3,350'
 COMM. December 29, 1967
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COMP. January 7, 1968

COUNTY Barton
 KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas

KANSAS			

CASING

20	10
15	8-5/8" 282' cemented w/170 sx cement
12	6
13	5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

ELECTRIC LOG TOPS:

Post Rock & Top Soil	70		
Shale & Clay	283	Anhydrite	835 + 1,035
Shale	825	Base Anhydrite	864 + 1,006
Anhydrite	865	Topeka	2,728 - 858
Shale & Shells	990	King Hill	2,851 - 981
Shale & Red Bed	1,480	Queen Hill	2,915 - 1,045
Shale	1,525	Heebner	2,999 - 1,129
Lime & Shale	1,710	Toronto	3,018 - 1,148
Lime	2,020	Douglas	3,031 - 1,161
Lime & Shale	2,795	Brown Lime	3,082 - 1,212
Lime	2,865	Lansing	3,090 - 1,220
Lime & Shale	2,930	Base K. C.	3,315 - 1,445
Lime	3,350	Conglomerate	3,328 - 1,458
Rotary Total Depth	3,350	Arbuckle	3,341 - 1,471
		Log T. D.	3,350 - 1,480
		Rotary T.D.	3,350 - 1,480

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

Arlo B. Romer

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 10th day of January, 1968.

Martha Hartpence
 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971