


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 5 Twp. 28S Rge. 20 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW SW
Lease Owner K.R.M. Petroleum Corporation
Lease Name Fromme Well No. 1
Office Address 817 Seventeenth St. - Denver, Colorado 80202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed June 25, 1977
Application for plugging filed June 25, 1977
Application for plugging approved June 25, 1977
Plugging commenced June 25, 1977
Plugging completed June 25, 1977
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bud Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5015
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	621'	8 5/8"	621'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug with 40 sacks cement at 660',
20 sacks at 240', 12 sacks at 40'
3 sacks in rat hole. Job completed
at 3:00 P.M., June 25, 1977 by
Halliburton.

RECEIVED
JUN 28 1977 6-28-77
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Search Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.
R. M. Stagl (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. M. Stagl
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1977

Maxine Dressen
Maxine Dressen Notary Public.

My commission expires February 22, 1981



DRILLERS LOG
FROMME #1

<u>CASING RECORD:</u> 8 5/8" set at 621' with 275 sack HOWCO Light and 200 sacks common cement	<u>OPERATOR:</u> K.R.M. Petroleum Corporation	<u>DESCRIPTION:</u> C NW SW Section 5-28S-20W Kiowa County, Kansas
<u>TOTAL DEPTH:</u> 5015'	<u>CONTRACTOR:</u> Search Drilling Company	
	<u>COMMENCED:</u> June 14, 1977	
	<u>COMPLETED:</u> June 25, 1977	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	155	
Sand, Shale and Clay	155	640	
Red Bed and Shale	640	1218	
Red Bed and Shale	1218	1359	
Anhydrite and Shale	1359	1772	
Shale and Lime	1772	2096	
Shale and Lime	2096	2524	
Lime and Shale	2524	3070	
Shale and Lime	3070	3160	
Lime and Shale	3160	3808	
Shale and Lime	3808	4338	
Lime and Shale	4338	4480	
Kansas City	4480	4595	
Lime and Shale	4595	4947	
Lime and Shale	4947	5015	
Rotary Total Depth	5015		D & A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

R. M. Stagl
R. M. Stagl

Subscribed and sworn to before me this 27th day of June, 1977.

My appointment expires;
February 22, 1981

Maxine Dressen
Maxine Dressen Notary Public

