


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Kiowa County, Sec. 7 Twp. 28S Rge. 20W
Location as "NE/CNW1SW1" or footage from lines
C-NE NE

Lease Owner Belama Oil Company
Lease Name Toner Well No. 1
Office Address Suite 1830, One Williams Pl., Tulsa, O
Character of Well (Completed as Oil, Gas or Dry Hole) 74103
Dry Hole

Date Well completed June 25, 1978
Application for plugging filed Verbal Application 1978
Application for plugging approved Verbal Approval 1978
Plugging commenced June 25, 1978
Plugging completed June 25, 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 5,030
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | 6-30-78 | | | 8-5/8" | 652' | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 5,030 ft. (rotary total depth) to 650 ft. Set plug at 650 ft. and cemented with 65 sacks cement. Filled hole with heavy rotary mud from 650 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.


Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 28th day of June, 1978

My commission expires June 30, 1978

Elsie Willison - Notary Public.

KANSAS DRILLERS LOG

COMPANY Belama Oil Company

SEC. 7 T. 28S R. 20W

FARM Toner

NO. 1

LOC. C-NE NE

COUNTY-KIOWA

ROTARY TOTAL DEPTH 5,030'

COMM. June 12, 1978

COMP. June 25, 1978

CONTRACTOR H-30, Inc.

ISSUED June 28, 1978

CASING

10 3/4"

8 5/8" Set at 652' cemented w/525 sxs cement.

ELEVATION 2,328 K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|--------------------|--------|
| Sand and Shale | 525' |
| Anhydrite | 652' |
| Shale | 990' |
| Shale and Lime | 2,500' |
| Lime and Shale | 5,030' |
| Rotary Total Depth | 5,030' |

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th day of June, 1978.

WILLISON
NOTARY
JUN 30 1978

Elsie Willison
Elsie Willison Notary Public

My Commission Expires:

June 30, 1978