

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

KIOWA

County. Sec. 24 Twp. 30S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines C W 1/2
Lease Owner SHELL OIL COMPANY
Lease Name ROBBINS UNIT Well No. 1-24
Office Address 1845 Sherman Street, Denver 3, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 2, 1961
Application for plugging filed February 2, 1961
Application for plugging approved February 2, 1961
Plugging commenced February 2, 1961
Plugging completed February 2, 1961
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, R.R. #1, Stafford, Kansas.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surf. Clay, Sand & Redbed	Surf. Csg.	-0-	415'	8-5/8"	415'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED:

Filled hole with heavy mud 4701' up to 375'. Bridged using 1/3 sk. hulls, Halliburton Plug. Plugged 35 sx. cement through drill pipe by Halliburton. Filled hole with heavy mud up to 35'. Bridged with 1/2 sk. hulls, Halliburton Plug. Plugged with 15 sx. cement through drill pipe by Halliburton to 4' below Ground Level.

Job Completed: 6:30 p.m. February 2, 1961.

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1961 2-6-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

C. T. HONAKER

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker T. HONAKER, DRIG. SUPT.

BOX 232, RUSSELL, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 61

Notary Public.

My commission expires 10-17-63



SHELL OIL COMPANY - Operator

SIERRA PETROLEUM CO., INC. - Contractor

ROBBINS UNIT #1-24
 C W $\frac{1}{2}$
 Sec. 24-30S-16W
 Kiowa County, Kansas

T. D.: 4701'
 Elev.: 1779' K.B.

Commenced: 1-18-61
 Completed: 2-2-61

Casing:

8-5/8" Set at 415' K.B.

Cement:

with 300 sx. cement

FORMATION

DEPTH

Surface Clay & Sand	60'
Red Bed	415'
Red Bed & Gypsum	655'
Anhydrite	680'
Shale & Shells	850'
Salt & Shale	1000'
Shale, Shells & Gypsum	1115'
Shale & Shells	1530'
Shale, Shells & Gypsum	1900'
Shale, Gypsum & Lime	2060'
Lime & Shale	3936'
Lime	4305'
Lime & Shale	4415'
Lime	4401'
Lime & Shale	4582'
Viola	4701'

TOPS:

Anhydrite	655'
Heebner	3748'
Lansing Kansas City	3938'
Marmaton	4356'
Cherakee	4449'
Mississippi	4500'

RECEIVED
 STATE CONSERVATION COMMISSION
 FEB 6 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C.T. Honaker

Subscribed and sworn to before me this 3rd day of February 1961.

LeRoy Dietz
 Notary Public

My Commission Expires: 10-17-63