

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas



WELL PLUGGING RECORD

Kiowa County, Sec. 17 Twp. 30 Rge. 16 (W)

Location as "NE/CNW/SW" or footage from lines CSE/4  
Lease Owner Barbara Oil Company  
Lease Name Rice-Robbins Well No. 1  
Office Address 322 Central Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed February 28, 1961  
Application for plugging filed February 28, 1961  
Application for plugging approved February 28, 1961  
Plugging commenced February 28, 1961  
Plugging completed February 28, 1961  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5163 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	220	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud from 5163 to 300. Wood plug at 300'. 30 sacks cement, mud to 25'. Wood plug 25 sacks cement to base cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 15 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L.W. Davidson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.W. Davidson  
322 Central Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 61

My commission expires March 2, 1965  
Mildred Fisher Notary Public.



ROTARY DRILLING LOG

COMPANY: Barbara Oil Company  
322 Central Building  
Wichita, Kansas  
LOCATION: C SE/4 Sec. 17-30S-16W, Kiowa County, Kansas  
Rice-Robbins #1 Well

Rotary Drilling Commenced 2-2-61

Rotary Drilling Completed 2-28-61

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Ran 8 jts 13 3/8" Spiralweld Casing. Set @ 317' with 300 sacks cement. Circulated.  
D&A, no oil string.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50'	Clay, shale			
95'	Sand, shale			
175'	Shale			<u>Circulate for Samples</u>
325'	Red bed	4578'	4890'	
905'	Red Bed, shale	4760'	4950'	
935'	Anhydrite	4775'	4966'	
1010'	Shale	4806'	5073'	
1095'	Shale, shells, salt	4856'	5082'	
2060'	Shale, shells	4875'	5102'	
2190'	Lime, shale	4882'	5145'	
2900'	Lime			<u>Slope Test</u>
3520'	Lime, shale			
3641'	Lime	127'	0°	
3730'	Lime, shale	1000'	0°	
3910'	Lime	1500'	0°	
3985'	Sandy lime	2000'	0°	
4055'	Lime	2500'	0°	
4110'	Sandy lime, shale	3000'	0°	
4175'	Sand, shale, lime	3500'	0°	
4230'	Lime, shale			
4300'	Shale, lime			<u>S.L.M.</u>
4465'	Lime, shale			
4560'	Lime	3435'	OK	
4670'	Lime, shale			
4687'	Shale, lime			
4760'	Lime, shale			
4783'	Shale, lime			
4800'	Lime, shale			
4806'	Miss. chert			
4849'	Miss.			
5035'	Viola	5060'	Simpson shale	
5049'	Lime, shale	5127'	Simpson	
		5165'	Arbuckle T.D.	

RECORDED  
INDEXED  
MAR 10 1961  
WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
By C. W. Sebitts  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 8th day of March, 1961, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

Marilyn A. Davis  
Notary Public  
Marilyn A. Davis