

WELL PLUGGING RECORD

Give AFI Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat**

McPherson County. Sec. 31 Twp. 19 Rge. 2 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW SE
Lease Owner Veeder Sup. & Dev. Co.
Lease Name McBride Well No. 1
Office Address Cherryvale, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 6-20-46 19
Application for plugging filed 6-20-46 19
Application for plugging approved 6-20-46 19
Plugging commenced 6-21-46 19
Plugging completed 6-21-46 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production Dry Hole 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3039 Feet
 Show depth and thickness of all water, oil and gas formations.
 OIL, GAS OR WATER RECORDS CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole filled with heavy rotary mud except at cement plugs. 20 sacks cementspotted at 200' up and 5 sacks of cement at top of surface pipe.

3-13-48

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Veeder Sup. & Dev. Co.
Address Cherryvale, Ks.

STATE OF Indiana COUNTY OF Adams, ss.
Donald J. Adams (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God. Don't know what I'm doing

(Signature)

By Gordon & Adams

Chengzhe 12
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of March 1948 (Address)

My commission expires 11-5-51

Notary Public.

PLUGGING
FILE SEC 31 T 19 R 22
BOOK PAGE 59 LINE 26

Veeder Supply & Dev'l. Co.

Cherryvale, Kansas

Drilled for Fawcett Drilling Company Farm McBride No. 1 Depth 3039'
 Contractor Veeder Supply & Development Co. Pipe 159' of 8 5/8", 32# Surface Pipe
 Location SE/4 Sec. 31 Twp. 19S Range 2W
 Commenced 5-31-46 Completed 6-20-46 County McPherson State Kansas

FORMATION LOG

Soil & Clay	0	30	30
Sand	30	65	35
Clay	65	140	75
Blue Shale	140	154	14
Shale & shells	154	265	111
Sandy shale & shells	265	375	110
Lime & shale	375	520	145
Sandy shale & lime	520	645	125
Sandy shale	645	770	125
Sandy lime	770	805	35
Sandy lime & shale	805	870	65
Lime & shale	870	965	95
Shale & shells	965	1050	85
Sandy shale & lime	1050	1360	310
Shale & shells	1360	1455	95
Lime & shale	1455	1545	90
Shale, grey	1545	1605	60
Shale & shells	1605	1720	115
Lime & shale	1720	1965	245
Shale & shells	1965	1993	28
Lime	1993	2020	27
Shale & lime	2020	2050	30
Lime	2050	2090	40
Lime & shale	2090	2350	260
Shale	2350	2378	28
K. C. Lime	2378	2400	22
Lime & shale	2400	2845	467
Shale	2845	2890	45
Lime & shale	2890	2925	35
Shale & shells	2925	2985	60
Lime & shale	2985	3028	43
Lime	3028	3039	11

TOTAL DEPTH - 3039 Feet

31 19 26
59 26AFFIDAVIT

STATE OF KANSAS)
 MONTGOMERY COUNTY) ss:

EMMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the McBride #1 well in Section 31-19S-2W, McPherson County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY,

By: Emmett C. Veeder

President.

Subscribed and sworn to before me this 28th day of June, 1946.

Charles L. Courard
 Notary Public

My Commission Expires: July 11, 1948