

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.113.00244.00.00

API NUMBER C-07617

LEASE NAME Finkle

WELL NUMBER 1

4880 Ft. from S Section Line

3020 Ft. from E Section Line

SEC. 23 TWP. 19 R. 2 (E) or (W)

COUNTY McPherson

Date Well Completed 3-29-92

Plugging Commenced 1-16-92

Plugging Completed 1-20-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Robert A. Anderson

ADDRESS 1448 N. High Dr., McPherson, Ks. 67460

PHONE# (316) 241-1861 OPERATORS LICENSE NO. 05696

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 14, 1992 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? Was sent in with plugging application

Producing Formation Viola Depth to Top 3373' Bottom 3390' T.D. 3390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	202'	10 3/4"	202'	0
Viola		0	3373'	7"	3373'	438'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill with rock & sand to 3333'. Dump 10 sacks of cement with bailer on sand. Push rubber plug to 2100'. Dump 10 sacks on plug. Build bridge at 300'. Dump 2 yards of slurry mix at 300'. 1-17-92. 1-20-92, Dump 5 yards ready mix cement filling surface to bottom of cellar.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address Box 341, Canton, Kansas 67428

STATE OF Kansas COUNTY OF McPherson, ss.

Robert A. Anderson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

(Signature) Robert A. Anderson

(Address) 1448 N. High Dr. McPherson Ks 67460

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 92

Marlene F. Unruh
Notary Public

My Commission Expires: 7-29-93

