

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

3400'

Operator's Full Name Woodman & Iannitti Drilling Company  
Complete Address 1008 Union National Bldg., Wichita, Kansas  
Lease Name Eikmeier Well No. 1  
Location C SW NW Sec. 4 Twp. 23 Rge. (E) (W) 18  
County Pawnee Total Depth 4390'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated (OWWO)  
Plugging Contractor Russ casing Pulling  
Address Box 1082 Great Bend, Kansas License No. 623  
Operation Completed: Hour 10 A Day 11 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 268' cwc

5 1/2 csg set at 4372' cw 100 sk cmt.

5 1/2 csg PBD 4362' with perf. (4335 1/2 - 4337 1/2)

Filled 5 1/2 csg W/sd (4300-4362) dumped 5 sk cmt W/dump bailer. (4265-4300)

Cutoff and recovered 3400' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug  
and pumped 130 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murrin  
Well Plugging Supervisor

INVOICED

DATE 8-15-72

INV. NO. 6159-42