

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

10-30-1970
RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza, Wichita, Kansas 67202

Lease Name Hanson Well No. 1

Location NW SE NE Sec. 15 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3761

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.

Operation Completed: Hour 5:30 A Day 28 Month 10 Year 1970

The above well was plugged as follows:

RTD 3761' 8 5/8 csg set at 284' cwc 180 sk. Gmt. Mat. 85 sk reg poz 6%.

Gunned pits, circulated heavy mud, set cementing plug at 420' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. F. Massey
Well Plugging Supervisor

DATE 10-30-70

INV. NO. 2776-W