

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1978

P

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,533

CONSERVATION DIVISION
Wichita, Kansas
8-17-1978
(of this well)

Operator's Full Name Rupe Oil Co., Inc.

Complete Address Box 2273, Wichita, Kansas

Lease Name Hanson Well No. 2

Location SW NW NE Sec. 15 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3811'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5.45 P Day 11 Month 8 Year 1978

The above well was plugged as follows:

RTD 3811' 8 5/8 csg set 282' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 650' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8-18-78

INV. NO. 78741-W