

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1974

CONSERVATION DIVISION  
Wichita, Kansas

5-24-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Glen Rupe  
Complete Address 200 West Douglas, Wichita, Kansas 67202  
Lease Name Hanson (OWWO) Well No. 1  
Location SW SW NE Sec. 15 Twp. 20 Rge. (E) (W) 16  
County Pawnee Total Depth 3960'  
Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 12N Day 22 Month 5 Year 1974

The above well was plugged as follows:

Total depth 3960' 8 5/8 csg set at 1068' cwc.

4 1/2 csg set at 3960' cw 200 sk.

4 1/2 csg PBTD 3758' with top perf. (3751')

Pumped down 4 1/2 csg with 10 sk cem. W/100 lbs hulls. Top of cem. 3005'.

Cutoff and recovered 2942' of 4 1/2 csg.

Filled 8 5/8 csg with mud to 375' -set rock & sand bridge (375-365)

Filled with readymix cement from 365' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 9/9/74

INV. NO. 5/30/74