

15.187.10033.00.00

Form CP-3
Rev. 6-26-62

VP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1964

CONSERVATION DIVISION
Wichita, Kansas

3-31-1964

Operator's Full Name Superior Oil Company
Complete Address: Box 200 Casper, Wyoming
Lease Name Weaver Unit Well No. # 2
Location C SW/4 Sec. 35 Twp. 30S Rge. (E) (W) 42
County Stanton Total Depth 5258'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kansas License No. 49
Operation Completed: Hour 3 PM Day 28 Month 3 Year 64

The Above well was plugged as follows:

8 5/8"-1518' Circulated w/cement. 4 1/2"-5258' Cemented w/200 Sax.cement.
Perforations 5216' to 5230' Plug back to 5234'
Plug bottom w/sand 5234' to 5200' 5 Sax.cement 5200' to 5140'
Mud 5140' to 1530' 50 Sax.cement 1530' to 1380'
Pulled 2460' 4 1/2" Pipe. Company Plug bottom. Halliburton Pump mud and
50 Sax.cement. Well to be used as a Disposal Well.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Hughes*
Well Plugging Supervisor

DATE 3/31/64

INV. NO. 8844-4