

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1968
CONSERVATION DIVISION
Wichita, Kansas

2-12-1968

Operator's Full Name The Superior Oil Company

Complete Address: Box 200, Casper, Wyoming 82601

Lease Name Weaver Unit Well No. 1

Location C NW/4 Sec. 35 Twp. 30 Rge. 42 (E) (W)

County Stanton Total Depth 5335'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 7 Month 2 Year 1968

The Above well was plugged as follows:

10 3/4" to 1518' circulated w/ cement. 7" to 5335' cemented/

Top perforations 5203' Plug bottom w/ 25sacks cement.

Top of cement 4762' Mud 4762' to 800'

Spotted 50 sacks cement 800' to 700' Mud 700' to 35'

Plug, Hulls & 15 sacks cement 35' to 0' Company Pump

Pulled 2824' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/13/68
INV. NO. 7257-W