

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

8-5-1968  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Superior Oil Co.

Complete Address: Box 200, Casper, Wyoming 82601

Lease Name R.H.C. Unit Well No. 2

Location C SE Sec. 34 Twp. 30 Rge. 42 (W)

County Stanton Total Depth 5400'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Sante Fe Pipe & Supply Co.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 4:00Pm Day 31 Month 7 Year 1968

The Above well was plugged as follows:

8 5/8" to 1511' circulated w/ cement. 5 1/2" to 5229' cemented.

Top perforations 5208' Plug bottom w/ 10 sacks cement.

Top of cement 5115' Mud 5115' to 750'

Spotted 35 sacks cement 750' to 650' Mud 650' to 40'

Plug, Halls & 10 sacks cement 40' to 0' Company Pump

Pulled 3011' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/5/68  
INV. NO. 8233-u