

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1968
CONSERVATION DIVISION
Wichita, Kansas

8-15-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Superior Oil Company

Complete Address: Box 200, Casper, Wyoming 82601

Lease Name R.H.G. Unit Well No. X 1

Location ~~B/S~~ C NE Sec. 33 Twp. 30 Rge. 42 ~~W~~ (W)

County Stanton Total Depth 5356'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 12 Month 8 Year 1968

The Above well was plugged as follows:

10 3/4" to 1527' circuited w/ cement. 7" to 5352' cemented.

Top perforations 5252' Plug bottom w/ 25 sacks cement.

Top of cement 5000' Mud 5000' to 900'

Spotted 50 sacks cement 900' to 750' Mud 750' to 35'

Plug, Halls & 15 sacks cement 35' to 0' Company Pump

Pulled 2327' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/15/68

INV. NO. 8286-4