



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

30 September 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-097-20,769-0000

Dear Sir:

Mr. Jack Foy of Abercrombie Drilling Rig #11 has this date requested permission to plug the following described well:

Operator's Full Name: Morice L. Brown Inc.

Complete Address: Box 11320 Kansas City Mo. 64112

Lease Name: H. L. Byron Well No. 1

Location: SW NW Sec. 31 Twp. 30S Rge. 17W (E) (4)

County: Kiowa Total Depth: 5180

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Foy was instructed to plug the well as follows:

There is 1023' of 8 5/8" surface casing cemented. They circulated heavy mud at 1050' for 10 min. 1st plug 1050 with 50 sbs cement 2nd Plug pushed rubber plug to 1000' put 1/2 sbs hulls + 40 sbs cement on top of rubber plug. 3rd plug 40' to 0' on solid bridge with 10 sbs of cement. Plugging accomplished by Halliburton Co out of Pratt, Kans. Put 5 sbs cement in rat hole.

Very truly yours,

Paul Luth
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1981
CONSERVATION DIVISION
Wichita, Kansas