

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 - 1965
8-2-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Elmer Rider of K & E Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kans.

Lease Name: Frank Nichols Well No. # 1

Location: 150' S of C E/2 SW Sec. 1 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 5060' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

432' of 8 5/8" surface pipe, cemented with 375 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 with 25 sacks. Fill hole with
drilling mud to 40', 2nd cementing plug, bridge with hulls,
and cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving