

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 CONSERVATION DIVISION
 DEC 19 1966
 12-19-66
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this
 date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name: Nichols Well No. # 1

Location: C S/2 SE Sec. 1 Twp. 30 Rge. 18 (E)(W) W

County Kiowa County Total Depth 4959' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

275' of 8 5/8" surface Pipe, cement circulated with 275 sacks. (Error
on surface pipe). Fill hole with drilling mud to 275': 1st cementing
plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole
with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hull
and cement with 10 sacks to base of cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent