

15.009.07231.0000

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963
12-2-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. G. R. Kelsey of Lario Oil & Gas Co. has this

date requested permission to plug the following described well:

Mr. Lario Oil & Gas Co. guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita 2, Kansas

Lease Name: Meyer "A" Well No. # 5

Location: NW SW SW Sec. 13 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3300 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. R. E. Smith was instructed to plug the well as follows:

8 5/8" 222' Cwc.

Sanded hole back to 3250' & 5 sx cement wh/dump bailer.

Pulled pipe; set plug @ 210'; dumped 5 sx cement on plug

wh/dump bailer; allowed to set over-nite. Bailed hole dry;

displaced 20 sx cement. Mud to 40'; set rock bridge, &

displaced 10 sx cement, cementing to base of cellar.

Very truly yours,
Dani T. ...
Conservation Division Agent