

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 27 1964

3-27-64
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. K. W. Bungarner of Gulf Oil Corp. has this

date requested permission to plug the following described well:

Mr. H & H Tank Cleaning guarantees payment of the plugging fee.

Box 327, Chase, Kansas

Operator's full Name: Gulf Oil Corporation

Complete Address: 316 Union Center Bldg., Wichita, Kansas

Lease Name: Mary Meyer Well No. # 1

Location: C SW SW SE Sec. 13 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3262 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Noel Knight was instructed to plug the well as follows:

10 3/4" 127' Gwc.

Sanded hole back to 3240' & 5 sax cement with dump
bailer. Circulated hole with mud @ 350'; pulled pipe to
200'; displaced 30 sax cement thru pipe with mud pump.

Pulled remaining pipe; set rock bridge @ 30' & displaced
15 sax cement, cementing to base of cellar.

Very truly yours,

Law Tamm
 Conservation Division Agent