



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1973

CONSERVATION DIVISION  
Wichita, Kansas

7-6-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Monroe of Clinton Oil Company has this  
date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas 67202

Lease Name: Louis Hauser Well No. # 3

Location: NE NE Sec. 16 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3306 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dale Speers was instructed to plug the well as follows:

8 5/8" csg. 227' Cwc. Perf. 3100'.

Sanded hole back to 3050' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud, 1 sax hulls, & 100 sax

cement with Sun Cementing Company's pump truck, cementing from 320'

to base of cellar.

Very truly yours,

Dale Speers  
Conservation Division Agent