

State of Kansas



15.159.02783.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
SEP 28 1966  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

September 24, 1966

9-29-66

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: R. D. Olson

Complete Address: 353 Armour, Wichita, Kansas

Lease Name: Woodmansee Well No. 3

Location: NE SW NE Sec. 22 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3395' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3380' and cement with 5 sacks.

Fill hole with mud to 180'. Set rock bridge from 180' to 170' and cement

hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from

40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]  
Conservation Division Agent