

State of Kansas



15.159.19445.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1967

June 23, 1967 CONSERVATION DIVISION
Wichita, Kansas
7-3-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Russell, Kansas 67665

Lease Name: Woodmansee Well No. 1

Location: NE NW NE Sec. 22 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3404' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

- Fill hole with sand to 3050' and cement with 5 sacks.
- Pull 5 1/2" casing to 250'. Pump 5 sacks gel-mud through casing at 250'.
- Pull 5 1/2" casing to 200'. Pump 35 sacks cement through casing at 200'.
- Full remainder of casing. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William J. Lawrence
Conservation Division Agent