



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

November 2, 1969

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1969

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

11-10-69

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman- Iannitti Drlg. Co. has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Vess & Parks

Complete Address: 421 First Nat'l Bldg, Wichita, Kansas 67202

Lease Name: Rosa Bryant Well No. 1

Location: NW NW SW Sec. 22 Twp. 20 Rge. 10 (E) (W) X

County: Rice Total Depth 3381' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Fill hole with mud to 165'. Push plug and 1/4 sack hulls to 165' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent