

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 14, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1964

8-25-64

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ben Thompson of Apex Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Muir-Thompson Inc.

Complete Address: 201 Garlinghouse Bldg., Topeka, Kansas

Lease Name: Gill Well No. 4

Location: NW SE NE Sec. 22 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 2468' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Thompson was instructed to plug the well as follows:

Push 5½" plug to 2330'. Fill hole with sand to 2320' and
cement with 5 sacks. Fill hole with Mud to 200'. Set
rock bridge from 200' to 190' and cement hole with 20
sacks. Fill hole with mud to 40'. Set rock bridge from
40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Walter J. Lomas