



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202  
March 6, 1981

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Don Popp of L. D. Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Estate of Icer Addis

Complete Address: Drawer 8038, Wichita, Kansas

Lease Name: Madden Well No. 1

Location: NW NE NW Sec. 22 Twp. 20 Rge. 10 (E) (W)

County: Rice Total Depth: 3404'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Popp was instructed to plug the well as follows:

8-5/8"-260'-250 sacks Fill hole with mud. Pump 30 sacks cement through  
drill pipe at 450'. Pump 30 sacks cement through drill pipe at 250'.  
Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap  
hole with 10 sacks cement. Cement rathole with 5 sacks cement.

Very truly yours,

Conservation Division Agent

STATE CORPORATION COMMISSION

MAR 16 1981  
3-16-81  
CONSERVATION DIVISION  
Wichita, Kansas