



15.009.22419.0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

August 14, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Merle Short of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Thomason Oil Company

Complete Address: 2700 Oak Street, Suite A, Hays, Kansas 67601

Lease Name: Koch Well No. 1

Location: C W/2 SW Sec. 7 Twp. 20 Rge. 11 (W)

County: Barton Total Depth: 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Short was instructed to plug the well as follows:

8 5/8" - 253' - 175 sacks Elev. 1783.66 Anhydrite 588-549'

Circulate hole and fill with mud. Pump 50 sacks cement through drill pipe at 540'. Pump 30 sacks cement through drill pipe at 250'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1981

CONSERVATION DIVISION
Wichita, Kansas

8-18-81

Phillip R. Dick
Conservation Division Agent