


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Kiowa County. Sec. 3 Twp. 30 Rge. 18 (X) (W)  
Location as "NE/CNW/SW" or footage from lines C NE 1/2 NE 1/2  
Lease Owner Drilling and Exploration Company, Inc.  
Lease Name Fincham Well No. 1  
Office Address 811 Union Center Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 12, 1959  
Application for plugging filed October 12, 1959  
Application for plugging approved October 12, 1959  
Plugging commenced October 12, 1959  
Plugging completed October 12, 1959  
Reason for abandonment of well or producing formation Dry and Abandoned

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4971 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None						
Surface Casing		0'	530'	8-5/8"	530'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled w/mud to 450', pushed H.O.W.C.O. wood plug to 450' w/drill pipe. Topped w/35 sacks cement on top of plug. Cement plug 450' to 350' in surface casing. Filled w/mud to 35', pushed H.O.W.C.O. wood plug to 35' w/drill pipe. Filled to surface w/cement, 10 sacks.

10-14-59

RECEIVED  
STATE CORPORATION COMMISSION

OCT 14 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mack Oil Company (Drilling Contractor) and Halliburton  
Address Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Karl A. Peterson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl A. Peterson  
811 Union Center Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 1959

E. Elizabeth H. Suttor  
Notary Public.

My commission expires May 6, 1961



DRILLING AND EXPLORATION COMPANY, INC.  
Dallas, Texas

DRILLERS WELL LOG

Fincham #1

Commenced R.D.: 9-19-59  
Completed R.D.: 10-12-59  
Total Depth: 4971'

C NE NE Sec.3-30S-18W  
Kiowa County, Kansas  
Elevation: 2133 K.B.  
Initial Production: D&A  
Contractor: Mack Oil Co.

Casing Record: 531' 8-5/8" OD Surface Casing

STRATA	DEPTH
Sand & Shale	0 - 135'
Shale & Shells	135 - 405'
Anhydrite	405 - 422'
Shale & Shells	422 - 530'
Shale	530 - 713'
Redbeds & Lime	713 - 1650'
Shale & Shells	1650 - 2120'
Shale & Lime	2120 - 2415'
Lime	2415 - 2690'
Lime & Shale	2690 - 2985'
Shale & Lime	2985 - 3790'
Lime	3790 - 4093'
Sandy Shale	4093 - 4264'
Lime & Shale	4264 - 4877'
Chert & Lime (Mississippi)	4877 - 4971'

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Harold L. Steincamp

Signed and sworn to in my presence this 13th day of October, 1959, by Harold L. Steincamp, a representative of Mack Oil Company.

Elizabeth L. Sutton  
Notary Public

My Commission expires: May 6, 1961