

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 3 TWP. 30s RGE. 18w E/W
Location as in quarters or footage from lines:
C of NE SE

Locate Well
correctly on above
Section Platt.

Lease Owner K & E Drilling Co.
Lease Name Parkin # 9SWD Well No. _____
Office Address 100 S. Main, Suite 300, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4/18/83
Plugging completed 4/21/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 5285'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	439'	none
				4 1/2"	5165'	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Squeezed 4 1/2" casing with 75 sacks common cement with 2% gel. Pumped plug
to 4175'. Shot casing at 3615', 3205', & 3000'. Pulled total of 93 joints.
Squeezed hole with 3 hulls, 15 gel, 70 cement, 10 gel, & 1 hull. Released plug
& displaced with 150 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 83



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1983

4-28-83

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center
Wichita, Kansas 67202

WELL NAME: PARKIN #9
LOCATION: C NE SE Sec. 3-30S-18W
Kiowa County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: February 21, 1968

CASING RECORD:
8-5/8" @ 439' w/300 sx.
4 1/2" @ 5165' w/packer shoe w/130 sx.
ROTARY TOTAL DEPTH: 5285'

COMPLETED: March 8, 1968
ELEVATION: 2099' Grd; 2105' D.F.;
2108' K.B.
PRODUCTION:

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Clay & Rock	125
Shale	359
Sand	396
Shale	432
Anhydrite	438
Shale & Red Bed	1277
Shale & Shells	2020
Lime	2769
Shale & Lime	2905
Lime	3283
Shale & Lime	3563
Lime	5098
Lime & Chert	5119
Lime	5285

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson H. L. Wilson



Subscribed and sworn to before me this 15th day of March, 1968.

Judie K. Eby
Judie K. Eby Notary Public.

RECEIVED
STATE CONSERVATION COMMISSION

NOV 24 1982
CONSERVATION DIVISION
Wichita, Kansas

